


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 30 Twp. 22S Rge. 16W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
330' FEL, 2310' FNL
Lease Owner Texas Oil and Gas Company
Lease Name Kirchgassner Well No. 1
Office Address Suite 300, 200 West Douglas, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed February 24, 1979 19
Application for plugging filed February 24, 1979 19
Application for plugging approved February 24, 1979 19
Plugging commenced 9:00 PM February 24, 1979 19
Plugging completed 10:45 PM, February 24, 1979 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4260'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Filled hole with heavy mud.
Pumped thru openended Drill Pipe
50 sacks at 420'; 25 sacks at 240';
solid bridge at 40' with plug and 1/2
sack hull s and 10 sacks to surface.
3 sakes in rathole. Used 50/50 Pozmix with
2% gel.

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1979

CONSERVATION DIVISION
Wichita, Kansas 28-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
Bernard Laudermilk (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk
Bernard Laudermilk, President
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1979



Charles M. Hall, Notary Public.

My commission expires

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG ----- KIRCHGASSNER #1
 Located: 2310' FNL, 330' FEL, Section 30-22S-16W,
 Pawnee County, Kansas

OWNER: Texas Oil and Gas Company
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 17, 1979
 COMPLETED: February 24, 1979

TOTAL DEPTH: 4260'

LOG	CASING RECORD
0 - 269 Sand and Shale	Ran 7 joints used 2 3/4", 8 5/8" casing,
269 - 630 Shale, Red Bed, Sand	254.56' set at 267' K.B. with 100 sacks
630 - 1082 Red Bed and Sand	Light and 150 sacks Common with 3 1/2 cc.
1082 - 1103 Anhydrite	Plug down at 3:15 AM, 2-18-79, by Allied.
1103 - 1845 Shale and Salt	
1845 - 2125 Shale	
2125 - 4115 Lime and Shale	
4115 - 4194 Chert Shale	
4194 - 4260 Lime and Shale with Chert and Sand	Plugged

RECEIVED
 STATE CORPORATION COMMISSION

FEB 28 1979

REGISTRATION DIVISION
 STATE OF KANSAS