

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Stafford County, Sec. 27 Twp. 22 Rge. 11 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE  
Lease Owner The Shallow Water Refining Company  
Lease Name Morris Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 9-9-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 9-12-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Justice  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3694 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	177'	None
				5 1/2"	3694'	2117'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to plug back @ 3462', pushed plug to 3270', sanded hole to and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing, bailed hole to 160', set rock bridge to 150' and dumped 35 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 15 sacks of cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of September, 1966

My commission expires May 20, 1968  
Milton J. Volin Notary Public.

15-185-19345-0000

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY J. H. FATLOCK

SEC. 27 T. 22 R. 11W

FARM Morris

NO. 1

LOC. NW NW NE

TOTAL DEPTH 3695

COMM. 2-9-51


COMP. 2-22-51

SHOT OR TREATED

CONTRACTOR Lewis Drlg.

ISSUED 3-24-51

COUNTY Stafford



CASING

10" 177' cem. w/191 sx.

ELEVATION

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, redbed	120
sand hrd.	130
redbed	540
anhyd.	565
shale red, shells	675
redbed, shale,	
shells	1035
shale & shells	1375
shale & shells	1440
shale, brn. lime	1500
brn. lime	2355
shale	2520
shale & brn. lime	2624
shale	2715
shale & lime	2812
lime	2935
shale & lime	2960
lime	3071
lime & shale	3305
lime	3510
lime & shale	3565
lime	3575
congl.	3601
lime cherty	3625
Simpson shale & sand	3684
Arbuckle	3695
Total Depth	

RECEIVED  
OIL & GAS CORPORATION COMMISSION

JUL 22 1966

CONSERVATION DIVISION  
WICHITA, KANSAS