

LEASE NAME Morris

WELL NUMBER 2 (OWWD)

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 27 TWP. 22S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 12-1-93

Plugging Completed 12-3-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chew Oil & Gas Co.

ADDRESS P. O. Box 90 Lyons, KS 67554-0090

PHONE# (316) 257-5587 OPERATORS LICENSE NO. 6153

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3692'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 286 | none |
| | | | | 5 1/2 | 3692 | 1934 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3200' & 5 sks cement. Shot @ 2417, 2097 & 1934. Pipe came loose, pulled pipe. Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel, 100# hulls, released plug, 100 sks cement. max pressure 600#, shut in @ 200#. 60/40 pos 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chew Oil & Gas Co.

STATE OF KANSAS COUNTY OF RICE, ss.

R. DARRELL KELSO

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of December

James Herzberg
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1993
CONSERVATION DIVISION-4
Wichita, Kansas
Rev 1588 05-88