


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 22 Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines. ^{NW} NE-NE-SW
Lease Owner Ray C. Fleming Sr.
Lease Name Sleeper "B" Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-17 19 59
Plugging completed 2-23 19 59
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	224	None
				5 1/2	3603	2469.75

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3595' - dumped 5 sks cement - bailed oil out of hole - mudded to 220' - set 10' rock bridge - bailed fluid down to rock bridge - dumped 20 sks cement - mudded to 35' - set 5' rock bridge - dumped 10 sks cement.

3-29-59
RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1959
CONSERVATION DIV.
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.
R. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Johnson

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 59

[Signature]

My commission expires Sept 15, 1961

Notary Public.

PLUGGING
FILE SEC. 21 T. 22 R. 11W
BOOK PAGE 15 LINE 4

DRILLING LOG

E. H. ADAIR OIL COMPANY

SLEEPER B # 1

CONTRACTOR: E. H. Adair

T. D. 3605

Casing: 8 5/8 @ 224' w/175 sx.

Commenced: 5/15/1953

Completed: 5/30/1953

County: Stafford

S.-21T.-22-R.-11

NW-NE-SW.

Production: 20 BOPH

Figures indicate bottom of formations

Sand	100
Shale	224
Shale	863
Shale	1380
Shale & Shells	1430
Shale & Shells	1490
Lime & Shale	1625
Lime & Shale	1706
Lime	1876
Lime	1895
Shale	1965
Shale	2026
Shale & Shells	2187
Shale & Shells	2319
Shale & Shells	2441
Shale & Shells	2541
Shale & Shells	2665
Shale & Shells	2790
Lime & Shale	2810
Lime	2898
Lime	2994
Lime	3067
Shale & Shells	3127
Shale & Shells	3197
Shale	3240
Lime	3316
Lime	3357
Lime	3408
Lime	3468
Lime	3517
Lime	3521
Cong.	3529
Viola Chert	3542
Chert	3549
Shale	3579
Shale	3600
Arbuckle	3605 T.D.

TOPS

Heebner	3075-1258
Brown Lime	3212-1395
Kansas City	3237-1420
Mar.	3486-1669
Conglomerate	3521-1704
Viola	3529-1712
Simpson	3549-1732
Arbuckle	3600-1783

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1959
CONSERVATION DIVISION
OKLAHOMA

CERTIFIED CORRECT

Kenneth W. Johnson
Kenneth W. Johnson

PLUGGING
THE SEC. 21 T. 22 R. 11W
BOOK PAGE 15 LINE 4