

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

STAFFORD

County. Sec. 21 Twp. 22S. Rge. 11 W (E)---(W)

Location as "NE/CNW&SW" or footage from lines SE SE NW

Lease Owner E. H. Adair and Ray Fleming.

Lease Name Sleeper Well No. 4-A

Office Address 1019 E. Second Street (Adair); 508 Petroleum Bldg. (Fleming)  
Wichita, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry-hole.

Date well completed 7-8 19 56

Application for plugging filed 7-8 19 56

Application for plugging approved 7-8 19 56

Plugging commenced 7-8 19 56


Plugging completed 7-8 19 56

Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

NORTH



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well R.M. Brundage, Box 283, Hoisington, Kansas.

Producing formation Depth to top Bottom Total Depth of Well 3620 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Copy of Drillers' log attached hereto).						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud to 240 feet; dumped 20 sacks of cement at 240 feet;  
Mud to 35 feet; 10 sacks of cement to surface.

7-14-56

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

Address 507 Union National Bank Bldg., Wichita 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Sherrill Compton (employee of owner or contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Sherrill Compton  
Sherrill Compton.  
1019 E. Second Street, Wichita 7, Kansas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July, 19 56.

My commission expires September 15, 1957.

L. Hill

Notary Public.

PLUGGING  
FILE SEC. 21 T. 22 R. 11W  
BOOK PAGE 78 LINE 17

E. H. Adair Oil Company  
 1019 East Second Street  
 Wichita 7, Kansas.

SESENW

E. H. Adair and Ray Fleming  
 No. 4-A, Sleeper  
 SE SE 1/4  
 Section 21-Twp. 22S. R. 11 W.  
 Stafford County, Kansas.

Comm.: 6-29-56  
 Comp.: 7-8-56 7-8-56  
 Contractor:  
 Murfin Drilling Co.  
 8-5/8 @ 244 ft. w/175 sx.

Elevation: 1817 K.B.

Figures indicate bottoms of Formations

Shale & sand	to	244	Shaley lime	to	3118
Redbeds		525	Limey shale		3133
Lime & shale		555	Shale		3224
Shale & redbed		870	Lime		3229
Anhydrite		895	Shale		3248
Shale & shells		1490	Lime		3497
Shale & lime		3000	Shale, limey		3537
Lime		3026	Conglomerate		3541
Shale		3031	Lime		3544
Lime		3086	Chert		3590
Black shale		3090	Shale		3602
Lime		3094	Shaley sand		3610
Shale		3106	Shale		3620

Certified correct:

*K. W. Johnson*  
 K. W. Johnson - Geologist.

RECORDED  
 JUL 14 1956  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

PLUGGING  
 FILE SEC. 21 T. 22 R. 11W  
 BOOK PAGE 78 LINE 17