


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 22 Rge. (E) 11 (W)
Location as "NE/CNW*SW*" or footage from lines SW-SE-NW
Lease Owner Ray C. Fleming Sr.
Lease Name Sleeper "A" Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced _____ 2-22 19 59
Plugging completed _____ 2-26 19 59
Reason for abandonment of well or producing formation Depleted
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8 5/8	223	None
				5 1/2	3599	2935.11

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3590' - dumped 5 sks cement - bailed oil off of fluid - mudded to 200' - set 10' rock bridge - bailed fluid down to rock bridge - dumped 20 sks cement - mudded to 35' - set 5' rock bridge - dumped 10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Johnson

SUBSCRIBED AND SWORN TO before me this 26th day of March, 1959

My commission expires Sept 15, 1961

Notary Public.

PLUGGING
FILE SEC. 21 T. 22 R. 11W
BOOK PAGE 15 LINE 5

L-O-G

E. H. ADAIR OIL COMPANY

SW-SE-NW Sec. 21-22-S-R.11-W.

SLEEPER # 2

Stafford County, Kansas

Commenced: March 16, 1953

Elevation: 1818 K.B.

Sand	0-45
Shale	45-65
Sand	65-75
Shale	75-228
Shale	228-547
Anhydrite	547-566
Shale	566-940
Shale	940-1395
Shale & Shells	1395-1445
Shale & Shells	1445-1525
Lime	1525-1600
Shale & Lime	1600-1610
Lime & Shale	1610-1760
Shale & Lime	1760-1830
Shale & Shells	1830-1860
Shale & Shells	1860-1933
Shale & Shells	1933-2108
Lime & Shale	2108-2260
Shale & Shells	2260-2406
Shale & Shells	2406-2530
Shale & Shells	2530-2617
Shale & Shells	2617-2790
Lime	2790-2875
Lime	2895-2929
Lime	2929-3039
Lime	3039-3075
Shale Heebner	3075-3080
Lime	3080-3106
Shale	3106-3188
Shale	3188-3213
Brown Lime	3213-3238
K.C. Lime	3238-3251
Lime	3251-3298
Lime	3298-3351
Lime	3351-3384
Lime	3384-3440
Lime	3440-3491
Lime	3491-3495
Shale	3495-3525
Shale	3525-3571
Shale	3571-3608
Shald	3608-3613

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1959
CONSERVATION DIVISION
Wichita, Kansas

T.D. Certified Correct

Kenneth W. Johnson
Kenneth W. Johnson

PLUGGING
FILE SEC. 21 T. 22 R. 11W
BOOK PAGE 15 LINE 5