

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22, 512-0000

LEASE NAME Northwest Sleeper

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line
NW NW NW

SEC. 21 TWP. 22S RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4-29-93

Plugging Completed 5-4-93

LEASE OPERATOR Lebsack Oil Production, Inc.

ADDRESS P.O. Box 489 Hays, Kansas 67601-0489

PHONE# (913) 625-3046 OPERATORS LICENSE NO. 5210

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 308' | none |
| | | | | 4-1/2" | 3630' | 2642' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3490' and 4 sacks cement. Shot pipe @2820', 2642'.

Plugged surface with 300# hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 100# hulls, released plug and 100 sks. cement, 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lebsack Oil Production, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of May

Irene Herzberg
Notary Public

My Commission Expires:



RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1993
OBSERVATION DEPARTMENT
Wichita, Kansas