


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 21 Twp. 22 Rge. (E) 11 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NE NW
Lease Owner E. H. Adair and R. G. Fleming
Lease Name Sleeper Well No. 1
Office Address 407 W-K-H Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 16, 1952
Application for plugging filed July 16, 1952
Application for plugging approved July 16, 1952
Plugging commenced July 16, 1952
Plugging completed July 16, 1952
Reason for abandonment of well or producing formation Barren



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Copy of well log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Placed wooden plug at 240', put 20 sx cemet on plug, filled hole with mud up to 35' of surface, placed wooden plug and filled hole with 10 sx cement up to surface.

Name of Plugging Contractor E. H. Adair Oil Company
Address Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Russell I. Baker (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Russell I. Baker (Address)

SUBSCRIBED AND SWORN to before me this 21st day of July, 1952

My commission expires September 15, 1953 Notary Public.

PLUGGING FILE SEC 21 T 22 R 10 W
31 4

7-23-52

E. H. ADAIR OIL COMPANY

Sec. 21 T. 22s R. 11 W

Sleeper No. 1

NW NE NW

Comn. 7/3/52 Comp. 7/16/52 Stafford County, Kansas

251' 8 5/8" s/csg, 175 sx cement

Elevation

1810 DF
1808 Gr

Sand	0-85
Shale	85-251
Shale & Sand	251-535
Anhydrite	535-558
Shale	558-1360
Shale & Shells	1360-1425
Lime & Shale	1425-1515
Shale & Shells	1515-1550
Lime & Shale	1550-1559
Lime	1559-1691
Lime & Shale	1691-1761
Lime	1761-1800
Lime & Shale	1800-1846
Shale & Shells	1846-2006
Lime	2006-2138
Shale & Shells	2138-2496
Lime & Shale	2496-2775
Lime	2775-3070
Heebner	3070-3075
Lime & Shale	3075-3240
Lime	3240-3526
Conglomerate	3526-3556
Simpson Shale	3556-3580
Arbuckle	3580-3600 Rotary

Certified Correct

Russell Baker

PLUGGING
 SEC 21 T 22 R 11 W
 BOOK PAGE 31 LINE 4

STAFFORD COUNTY, KANSAS
 DEPARTMENT OF REVENUE
 RECEIVED