


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

STAFFORD County. Sec. 31 Twp. 22S Rge. 11 (W)

Location as "NE/CNW/SW" or footage from lines. SE SE SE  
Lease Owner WESTERN PETROLEUM CO., INC.  
Lease Name SLEEPER Well No. 1  
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JANUARY 4, 1961  
Application for plugging filed JANUARY 4, 1961  
Application for plugging approved JANUARY 4, 1961  
Plugging commenced 10:00 A.M., JANUARY 4, 1961  
Plugging completed 1:00 P.M., JANUARY 4, 1961  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? YES, J. LOUIS BROCK, WEST KANSAS FIELD SUPERVISOR

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, ST. JOHN, KANSAS  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE WATER			100'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

FIRST PLUG SET AT 240', CEMENTED WITH 20 SACKS  
CEMENT. SECOND PLUG SET AT 35' WITH 10 SACKS CEMENT  
TO SURFACE.

1-11-61  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor WESTERN PETROLEUM CO., INC.  
Address 925 PATTON ROAD, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
GEORGE B. TURNER (employee of owner) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) George B. Turner  
GEORGE B. TURNER, DRILLING SUPT.  
WESTERN PETROLEUM CO., INC.  
925 PATTON ROAD, GREAT BEND, KANSAS

SUBSCRIBED AND SWORN TO before me this 10TH day of JANUARY, 19 61

My commission expires AUGUST 5, 1964

Luella F. Dwyer  
LUELLA F. DWYER Notary Public.

*Al*  
DRILLER'S LOG

COMPANY: WESTERN PETROLEUM Co., INC. LOCATION: SE SE SE  
 SEC. 21, T22S, R11W  
 CONTRACTOR: WESTERN PETROLEUM Co., INC. STAFFORD COUNTY, KANSAS  
 FARM NAME: SLEEPER ELEVATION: 1812' K.By.  
 COMMENCED: DECEMBER 16, 1960 CASING 8-5/8" AT 256' SET WITH  
 USED: 225 SACKS CEMENT.  
 COMPLETED: JANUARY 3, 1961

SAND AND SURFACE CLAY	95
RED BED	535
ANHYDRITE	560
RED BED AND SHALE	930
SHALE AND LIME	1280
SHALE, SHELLS, SALT	1400
SHALE AND LIME	1515
LIME AND SHALE	1750
LIME	1905
SHALE AND LIME	2010
LIME AND SHALE	2745
SHALE AND LIME	2845
LIME AND SHALE	2923
LIME	3075
LIME AND SHALE	3240
LIME	3510
CONG. LIME AND CHERT	3555
CHERTY LIME	3581
SAND AND SHALE	3617
SHALE LIME	3665
ROTARY TOTAL DEPTH	3665

RECEIVED  
 STATE COMMISSION  
 JAN 11 1961  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS }  
 COUNTY OF BARTON } SS

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

*George B. Turner*  
 GEORGE B. TURNER, DRILLING SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10TH OF JANUARY, 1961.

*Luella F. Dwyer*  
 LUELLA F. DWYER, NOTARY PUBLIC

MY COMMISSION EXPIRES: AUGUST 5, 1964.