

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 34 Twp. 22 Rge. 11 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE SE

Lease Owner WESTERN PETROLEUM CO., INC.

Lease Name GATES Well No. 2

Office Address BOX # 524 GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed DECEMBER 10 19 62

Application for plugging filed DECEMBER 10 19 62

Application for plugging approved DECEMBER 10 19 62

Plugging commenced DECEMBER 11 19 62

Plugging completed DECEMBER 11 19 62

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. JUSTUS

Producing formation Depth to top Bottom Total Depth of Well 3701 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	203	8-5/8"	12/1/62	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE TO 180' WITH ROTARY MUD. PUSHED HULLS AND WOODEN PLUG TO FLUID.

CEMENTED WITH 20 SXS. CEMENT THROUGH DRILL PIPE. FILLED HOLE TO 40' WITH ROTARY MUD.

PUSHED HULLS AND WOODEN PLUG TO FLUID. CEMENTED WITH 10 SXS. CEMENT.

JOB COMPLETED @ 3:45 PM, 12/11/62.

STATE CORPORATION COMMISSION

DEC 14 1962

CONSERVATION DIVISION
WICHITA, KANSAS

12-14-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF BARTON, ss.
F. L. COPELAND (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. L. Copeland

925 PATTON ROAD, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 11TH day of DECEMBER, 19 62

Ruth M. Kruckenberg
RUTH M. KRUCKENBERG Notary Public.

My commission expires JUNE 13, 1966



CASING RECORD: 10 JTS 8-5/8" 28# USED PIPE
 COMPANY: WESTERN PETROLEUM Co., INC.
 CONTRACTOR: WESTERN PETROLEUM Co., INC.
 TOTAL DEPTH: 3701'
 COMMENCED: DECEMBER 1, 1962
 DESCRIPTION: NE SE SE SECTION 34-T22S-RIIW STAFFORD COUNTY, KANSAS
 COMPLETED: DECEMBER 11, 1962
 ELEVATION: 1788 DF 1790 KB

FORMATION	FROM	TO	REMARKS
SAND	0	40	SPUDDED @ 12:30 PM, 12/1/62. RAN 10 JTS OF 8-5/8" 28# USED PIPE (196.96). SET @ 203' w/200 sxs 60x40 Pozmix HA5. PLUG DOWN @ 5:30 PM. CEMENT CIRCULATED.
SAND, GRAVEL	40	160	
RED BED	160	497	DST #1 3671-76'. OPEN 1 1/4'. GOOD BLOW. RECOVERED 890' FORMATION WATER. 1BHP 1215#/30 MIN., FBHP 1200#/1 1/4 HR., IFP 25#, FFP 370#, HH 1980#.
ANHYDRITE	497	520	
SHALE, SHELLS, SALT	520	955	SCHLUMBERGER RAN GAMMA RAY-INTEGRATED SONIC LATEROLOG. RAN SRS. D & A.
SHALE AND SHELLS	955	1455	
LIME AND SHALE	1455	2505	
SHALE AND LIME	2505	2845	
LIME AND SHALE	2845	3092	
SHALE AND LIME	3092	3247	
LIME AND SHALE	3247	3280	
LIME	3280	3565	
LIME AND SHALE CHERTY	3565	3600	
CHERT AND SHALE	3600	3620	
SHALE AND LIME	3620	3676	
LIME	3676	3701	
RTD	3701		

ELECTRIC LOG TOPS

ANHYDRITE	502	+1288
HEEBNER	3072	-1282
LANSING	3230	-1440
B/KC	3480	-1690
CONGLOMERATE	3530	-1740
VIOLA	3567	-1777
SIMPSON	3608	-1818
ARBUCKLE	3671	-1881
RTD	3701	-1911

RECEIVED
 STATE CORPORATION COMMISSION

DEC 14 1962

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOGATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

F. L. Copeland
 F. L. COPELAND, DRILLING SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 12TH DAY OF DECEMBER, 1962.

Ruth M. Kruckenberg
 RUTH M. KRUCKENBERG, NOTARY PUBLIC

MY COMMISSION EXPIRES JUNE 13, 1966.