

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County, Sec. 34 Twp. 22 Rge. 11 (E) X (W)

Location as "NE/CNW/SW" or footage from lines APPROX. SW NE NE

Lease Owner WESTERN PETROLEUM CO., INC.

Lease Name ESSEX Well No. #1

Office Address 925 PATTON ROAD

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JUNE 2 19 62

Application for plugging filed JUNE 2 19 62

Application for plugging approved JUNE 2 19 62


Plugging commenced JUNE 2 12:30 P.M. 19 62

Plugging completed JUNE 2 2:00 P.M. 19 62

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LA CAMP, STAFFORD

Producing formation Depth to top Bottom Total Depth of Well 3654 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	209	8-5/8"	5/23/62	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE TO 180' WITH ROTARY MUD. PUSHED WOODEN PLUG AND HULLS TO FLUID.

CEMENTED THROUGH DRILL PIPE WITH 20 SXS. OF COMMON CEMENT.

FILLED HOLE TO 35' WITH ROTARY MUD. PUSHED WOODEN PLUG AND HULLS TO FLUID.

CEMENTED WITH 10 SXS. OF COMMON CEMENT. JOB COMPLETED @ 2:00 PM 6/2/62

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF KANSAS, COUNTY OF BARTON, ss.

F. L. COPELAND (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. L. Copeland

925 PATTON ROAD, GREAT BEND (Address)

SUBSCRIBED AND SWORN TO before me this 4TH day of JUNE, 1962

My commission expires JUNE 27, 1965

James M. Becker Notary Public.

INVOICED

DATE 6/7/62

INV. NO. 5141-W

D R I L L E R S   L O G

15.185-11369-0000

#1 ESSEX

CASING RECORD: 5 JTS 8-5/8" 20# PIPE.	COMPANY: WESTERN PETROLEUM CO., INC.	DESCRIPTION: <sup>SW NE NE</sup> <del>SE NW SW</del> SECTION 34-T22S-R11W STAFFORD COUNTY, KANSAS
TOTAL DEPTH: 3654'	CONTRACTOR: WESTERN PETROLEUM CO., INC.	ELEVATION: 1794' DF 1797' KB
	COMMENCED: MAY 23, 1962	
	COMPLETED: JUNE 2, 1962	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
CLAY	0	15	SPUD 5:45 PM 5/23/62. RAN 5 JTS 8-5/8" 20# NEW PIPE (203.56'). SET AT 209' w/ 240 SXS. 60x40 POZMIX, 2% GEL AND 3 SXS. CACL AND 3 SXS. A.C PLUG DOWN 10:45 PM.
SAND AND CLAY	15	100	
SAND	100	120	
SHALE	120	125	
RED BED	125	500	
ANHYDRATE	500	520	
SHALE AND SHELLS	520	900	
SAND	900	950	
SHALE SHELLS SALT	950	1125	
SHALE AND SHELLS	1125	1565	
LIME AND SHALE	1565	1910	DST #1 3248 - 3320'. OP. 40". WEAK BLOW 5". REC. 15' MUD. NS. IBHP 495# FBHP160#/30", IFP 40#, FFP 60#.
SHALE LIME	1910	2090	
SHALE AND LIME	2090	2297	DST #2 3588 - 3620'. OP. 40". WEAK BLOW 7". REC. 15' ROTARY MUD w/ FEW OIL SPECKS. IBHP 780#/30". IFP-FFP 0#. HH 2300#. FBHP 120#/30".
LIME AND SHALE	2297	3245	
LIME	3245	3578	DST #3 648 - 3654. OP. 1 1/4'. STRONG BLOW 15" DIMINISHING TO WEAK BLOW AT END OF TEST. REC. 1035' CLEAR FORMATION WATER. NS. IBHP 1210#/30". FBHP1060#. IFP 50#. FFP 445#. HH2045#.
CHERT AND LIME	3578	3603	
LIME	3603	3620	
SHALE	3620	3636	
LIME AND SHALE	3636	3654	
RTD	3654		RTD 3654. D & A

ELECTRIC TOPS

ANHYDRITE	500	+1297
HEEBNER	3062	-1265
JATAN	3200	-1403
LANSING	3222	-1425
B/KC	3468	-1671
CONGLOMERATE	3518	-1721
VIOLA	3548	-1715
SIMPSON	3588	-1791
ARBUCKLE	3646	-1849

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 7 1962  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          )    SS  
COUNTY OF BARTON )

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

WESTERN PETROLEUM CO., INC.

*F. L. Copeland*  
F. L. COPELAND, DRLG. SUPT.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6TH DAY OF JUNE, 1962.

*Janice M. Becker*  
JANICE M. BECKER, NOTARY PUBLIC

MY COMMISSION EXPIRES: JUNE 27, 1965