

**TO:**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

**API Well Number:** 15-073-00366-00-00  
**Spot:** SWNESWSW      **Sec/Twnshp/Rge:** 31-23S-12E  
721 feet from S Section Line,      4403 feet from E Section Line  
**Lease Name:** FRANK NESBITT      **Well #:** B2  
**County:** GREENWOOD      **Total Vertical Depth:** 1880 feet

**Operator License No.:** 32296  
**Op Name:** COX, WILLIAM P. & LISA A. DBA B & L  
**Address:** 2367 KS HWY 58  
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1880		125 SX
SURF	8.625	100		75 SX

**Well Type:** OIL      **UIC Docket No:**      **Date/Time to Plug:** 02/03/2017 9:00 AM  
**Plug Co. License No.:** 33413      **Plug Co. Name:** TITUS WELL SERVICE LLC  
**Proposal Rcvd. from:** WILLIAM P. COX      **Company:**      **Phone:** (620) 437-6246

**Proposed Plugging Method:** WILL BE PLUGGED WITH CEMENT.

**Plugging Proposal Received By:** MICHAEL HEFFERN      **WitnessType:** NONE  
**Date/Time Plugging Completed:** 02/03/2017 1:00 PM      **KCC Agent:** MICHAEL HEFFERN

**Actual Plugging Report:**  
well flowing/ran rubber plug to 1652',determined well open in cattleman sand squeezed 40 sxs cement into formation let well set well quit flowing,tagged cement @ 1415' pulled tubing to 716' pumped 15 sxs cement,pulled tubing to 250',pumped 75 sxs cement to surface.gel spacers between cement plugs,casing shot @ 716' & 250' ,

**Perfs:**      **KCC WICHITA**  
**MAR 02 2017**  
**RECEIVED**  
  
**RECEIVED**  
**KCC DIST # 3**  
**FEB 27 2017**  
**CHANUTE, KS**  
  
*MH*

**Remarks:**  
  
**Plugged through:** TBG

**District:** 03      **Signed** *Mike Heffern*      **(TECHNICIAN)**

**INVOICED**  
**MAR - 3 2017**      Form CP-2/3

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



Cement or Acid Field Report  
 Ticket No. **3158**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
2-3-17	1008	Nesbet B #2	B 31	23 25S	12E	GW	Ks
Customer	Mailing Address	City	State	Zip Code	Safety Meeting	Unit #	Driver
B & L OIL	2367 KANSAS HWY 58	MADISON	Ks	66860	KM RL SM DG	102 110 114 141	RICK C. Steve M. Steve M. DAVE G.

Job Type P.T.A. <sup>old</sup> well Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8"  
 Casing Depth 1880' Hole Size 7 7/8 Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting: WELL flowing water to SURFACE. Cornish wire Line Set 5 1/2 CIBP Above BV Formation @ 1700'. WELL still flowing. Rig up to 5 1/2 casing. Pump 5 1/2 Rubber & followed it w/ wire line. (Injection Pressure 700 PSI @ 3 BPM) Plug Stopped @ 1652' = Cattleman Formation open. Called KCC Agent Mike Heffern, OK to Squeeze off Cattleman Perfs. Mixed 40 SKS CLASS 'A' Cement w/ 3% CACL2 @ 15.2#/gal = 8.5 BBL Slurry. Shut down. wash out Pump & Lines. Release Plug. Displace Plug to 1415' w/ 34.5 BBL water. FINAL Pumping Pressure = 1250 PSI. TAG Plug w/ wire line @ 1415. Shut in @ 700 PSI. (Bottom Plug = 25 SKS in 5 1/2 = 237, 15 SKS in Formation = 40 SKS Total). Shut well in for 1 1/2 HRS. Release Pressure. well dead, no flow. Cornish wire line Perforated 2 Holes @ 690' & 2 Holes @ 250'. RAN 2 3/8 Tubing to 716' Spot 15 SKS 60/40 Pozmix Cement w/ 4% GEL. PULL Tubing. RIG up to 5 1/2 casing. BREAK Circulation w/ fresh water. Circulate Cement to SURFACE FROM 250' to SURFACE w/ 75 SKS 60/40 Pozmix w/ 4% GEL. Job Complete.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	15	Mileage	3.95	59.25
C 200	40 SKS	CLASS 'A' Cement } Squeeze off Cattleman Perfs	15.00	600.00
C 205	100 #	CACL2 3%	.60 #	60.00
C 203	90 SKS	60/40 Pozmix Cement } 690' Plug = 15 SKS	12.75	1147.50
C 206	300 #	GEL 4% } 250' Plug 75 SKS	.20 #	60.00
C 108 R	5.75 TONS	Ton Mileage	M/c	345.00
C 113	4 HRS	80 BBL VAC TRUCKS	85.00	340.00
C 404	2	5 1/2 Top Rubber Plugs	70.00	140.00
THANK YOU			Sub TOTAL	3501.75
—M—			Less 5%	188.22
7.5%			Sales Tax	262.63

KCC WICHITA  
 MAR 02 2017  
 RECEIVED

Authorization witnessed By BILL Cox Title owner Total 3576.16

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.