

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-20455-00-01
Spot: SENWNW Sec/Twnshp/Rge: 16-30S-9E
4364 feet from S Section Line, 4246 feet from E Section Line
Lease Name: MKO RANCH Well #: 9
County: ELK Total Vertical Depth: 2600 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2600		175 SX
SURF	8.625	150		65 SX

Well Type: SWD UIC Docket No: E19844.1 Date/Time to Plug:
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: KEVIN WARDLOW Company: Phone: (620) 330-3666

Proposed Plugging Method: LAY OUT TUBING & PACKER, RUN TUBING TO BOTTOM & PUMP A GEL SPACER & PUMP A 50' CEMENT PLUG. PULL UP TO 1910' PUMP A 50' CEMENT PLUG. PULL UP TO 550' PUMP CEMENT TO SURFACE, LAY OUT TUBING & TOP OFF.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 02/16/2017 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2500' gelled hole and spotted 5 sack plug. Pulled up to 1800' and spotted 5 sack plug. Pulled 1" and perforated casing at 550'. Ran 1" back into 550' and circulated cement to surface. Pulled 1" and hooked onto casing and squeezed cement up the backside. A total of 160 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2536	2564		

RECEIVED
KCC DIST # 3
FEB 21 2017
CHANUTE, KS
DS
KCC WICHITA
FEB 27 2017

Remarks: WELL WAS PLUGGED DUE TO FAILED MIT.

Plugged through: TBG

RECEIVED
INVOICED
MAR - 6 2017

District: 03

Signed

Duane A. Sims

(TECHNICIAN)