

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-00192-00-02  
Spot: NENENE Sec/Twnshp/Rge: 16-33S-4W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: ALLEN Well #: 1OWWO  
County: SUMNER Total Vertical Depth: 4525 feet

Operator License No.: 32346  
Op Name: B5 OPERATING, LLC  
Address: PO BOX 45  
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2025		
COND	13	300		
PROD	4.5	2280		250 SX
SURF	10	305		175 SX
T1	2.375	2149		

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2016 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: MITCH BARTELSON Company: B5 OPERATING, LLC Phone: (620) 326-0486

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/29/2016 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 2025' & CAPPED WITH 2 SKS CEMENT. PERFORATED 4 HOLES AT 750'. PUMP BACKSIDE OF CASING WAS CEMENTED WHEN PIPE WAS SET. PUMPED 80 SKS CEMENT. STAGED WITH 25 SX TO 250#. STAGE 15 SX TO 300#. STAGE WITH 10 SX TO 350#. TOTAL 130 SKS.

Perfs:

Top	Bot	Thru	Comments
2166	2174		

Remarks: QUALITY WELL SERVICE. COMMON CEMENT.

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

Form CP-2/3

MAR - 3 2017

JK