

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-25789-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 25-27S-13W  
2990 feet from S Section Line, 384 feet from E Section Line  
Lease Name: NRSU Well #: 6  
County: PRATT Total Vertical Depth: 4335 feet

Operator License No.: 5364  
Op Name: BEREN CORPORATION  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3750		WITH 2 SX CMT
CIBP		4280		
PROD	5.5	4334	0	WITH 100 SX CMT
SURF	8.625	333		WITH 220 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2017 10:00 AM  
Plug Co. License No.: 34879 Plug Co. Name: CANAAN WELL SERVICE INC.  
Proposal Rcvd. from: CHARLES MILLER Company: BEREN CORPORATION Phone: (316) 215-2797

Proposed Plugging Method: SET CIBP @ 3750' & 2 SX CMT. PERFORATE 5 1/2" CASING AT 730'. CIRCULATE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS TO SURFACE FROM 730' WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/17/2017 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3750' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" CASING AT 730'. RUN TBG IN HOLE TO 730'. PUMPED DOWN TBG WITH 80 SX CMT FILLING 5 1/2" CASING TO SURFACE WITH CMT. SHUT IN TBG/CASING ANNULUS. HAD WEAK RETURNS OUT 5 1/2" X 8 5/8" ANNULUS. AFTER HAVING 50 SX CMT OUT BACKSIDE OF 5 1/2" CASING LOST RETURNS OUT 5 1/2" X 8 5/8" ANNULUS. PRESSURED UP TO 1000#. REVERSED & PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 100 SX CMT AT 1.25 BPM AT 200#. TBG/CASING ANNULUS WENT FROM 0-FAIR RETURNS. LAID DOWN TBG. CMT DOWN APPROXIMATELY 120'. ATTEMPT TO TOP OFF 5 1/2" CASING WITH 50 SX CMT. CMT WOULD CONTINUE TO STATIC OUT AT 120' FROM SURFACE. PUMPED DOWN CASING & SURFACE PIPE ANNULUS WITH 50 SX CMT. DID NOT CATCH ANY PRESSURE. SDON TO LET CMT SET. 2/17/17; TAGGED CMT AT 250'. TOPPED OFF WITH 30 SX CMT. TIED ON THE 8 5/8" X 5 1/2" ANNULUS & PUMPED 5 SX CMT. PRESSURED UP TO 1500#. CASING STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4319	4328		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

RECEIVED  
FEB 20 2017  
KCC DODGE CITY

Signed Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED Form CP-2/3

MAR - 8 2017