

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20954-00-01
Spot: SWNESENW Sec/Twnshp/Rge: 27-31S-33W
3301 feet from S Section Line, 3271 feet from E Section Line
Lease Name: BRIER LEASE Well #: 1-27
County: SEWARD Total Vertical Depth: 5649 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3780		WITH 2 SX CMT
PROD	4.5	5638	0	WITH 375 SX CMT
RBP		5000		
SURF	8.625	1534		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2017 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC
Proposal Rcvd. from: GREG KLAUS Company: BEREXCO Phone: (316) 772-8650

Proposed Plugging Method: CIBP @ TOF. PERFORATE AT 1580' WITH 50 SX CMT WITH 100# HULLS. PERFORATE AT 600' TO 0'.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2017 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

RCIBP @ 5000'. TOF @ 3931'. SET CIBP @ 3780' WITH 2 SX CMT. TEST CASING TO 500 PSI. HOLDING. PERFORATE AT 1570' WITH 50 SX CMT & 100# HULLS. PERFORATE AT 550' WITH 130 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5518	5533	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
FEB 27 2017
KCC DODGE CITY

INVOICED Form CP-2/3

MAR - 3 2017