

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-24327-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 32-7S-16W
557 feet from S Section Line, 881 feet from E Section Line
Lease Name: TAYLOR TRUST "A" Well #: 1-32
County: ROOKS Total Vertical Depth: 3350 feet

Operator License No.: 34579
Op Name: COBALT ENERGY LLC

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1086		450 sx

Address: 115 S. BELMONT #12 PO BOX 8037
WICHITA, KS 67208

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/07/2017 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-2379

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 02/07/2017 9:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3313 w/50 sx
2nd plug @1125 w/50 sx
3rd plug @600 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: QUALITY OILWELL

Plugged through: DP

District: 04

Signed _____



(TECHNICIAN)

INVOICED

Form CP-2/3

FEB 16 2017

MAR - 9 2017