

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40267-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 21-27S-6E
1064 feet from S Section Line, 2315 feet from E Section Line
Lease Name: TABING Well #: 3
County: BUTLER Total Vertical Depth: 3012 feet

Operator License No.: 6655
Op Name: CRAWFORD, GARRY F. DBA CRAWFO
Address: PO BOX 727
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2967		25 SX
SURF	8.625	63		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2017 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: BRANCE CRAWFORD Company: CRAWFORD PRODUCTION COMP Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 02/03/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE CUT TUBING @ 1850' & 900', LAYED DOWN 900' 2 3/8" TUBING. RIH W/ TUBING @ 890', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A COMMON & DISPLACED IN CASING. DID NOT TAG CEMENT. RIH W/ TUBING @ 890', CONSOLIDATED MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. 2-3-2017, TAGGED CEMENT @ 455'. RIH ON WIRELINE PERFERATED SQUEEZE HOLES @ 250-251;. RIH W/ TUBING @ 260' CONSOLIDATED ESTABLISHED CIRCULATION & MIXED & PUMPED 368 CLASS A COMMON TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET #52018.

Perfs:

Top	Bot	Thru	Comments
2967	3012	OH	

Remarks: DENIED TA / TUBING HUNG UP IN WELL. / LEFT 2100' TUBING IN HOLE.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

Form CP-2/3

INVOICED

MAR - 3 2017