

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-083-10183-00-00  
Spot: NESWSWSW Sec/Township/Rge: 9-21S-22W  
659 feet from S Section Line, 4626 feet from E Section Line  
Lease Name: COX Well #: 2  
County: HODGEMAN Total Vertical Depth: 4449 feet

Operator License No.: 32331  
Op Name: DK OPERATING INC.  
Address: 621 BENTON ST.  
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4447	0	WITH 75 SX CMT
SURF	8.625	200		WITH 130 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/15/2017 4:00 PM  
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.  
Proposal Rcvd. from: DOUG COSSMAN Company: DK OPERATING Phone: (620) 357-5345

Proposed Plugging Method: PLUG BOTTOM WITH 50 SX CMT & 200# HULLS. SHOOT OFF CASING & PULL OUT. RUN TBG & PLUG WITH CMT. PLUG AT 1450' WITH 50 SX CMT. PLUG AT 640' WITH 80 SX CMT. PLUG AT 240' WITH 50 SX CMT. USE 10 SX CMT TO TOP OFF.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2017 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

2/15/17: TRIED TO PULL CASING, PULLED 110,000 OVER & COULDN'T GET OUT OF HEAD. WAS GOING TO LOG BUT COULDN'T GET CASING TO LOAD. RUN TBG TO 3800' & PUMPED 100 SX CMT & 400# HULLS. PULLED TBG. 2/16/17: LOADED HOLE WITH FLUID. RAN BOND LOG. FOUND CMT 1350' TO SURFACE. RUN TBG TO 1450' & PUMPED 145 SX CMT. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & COULDN'T PUMP INTO.

Perfs:

Top	Bot	Thru	Comments
4447	4449	OH	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier

(TECHNICIAN)

RECEIVED  
FEB 21 2017  
KCC DODGE CITY MD

JA

INVOICED

MAR - 3 2017

Form CP-2/3