

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-22224-00-00
Spot: E2NWSWSE Sec/Twnshp/Rge: 31-29S-6W
990 feet from S Section Line, 2145 feet from E Section Line
Lease Name: SCHEER Well #: 2
County: KINGMAN Total Vertical Depth: 4197 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>35162</u>	<u>PROD</u>	<u>5.5</u>	<u>4240</u>	<u>2490</u>	<u>150 SX</u>
Op Name: <u>DIXON OPERATING COMPANY, LLC</u>	<u>SURF</u>	<u>8.625</u>	<u>225</u>		<u>185 SX</u>
Address: <u>8100 E. 22ND ST N BLDG 300, SUITE 20</u>	<u>T1</u>	<u>2.875</u>	<u>4156</u>		
<u>WICHITA, KS 67226</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2016 12:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGANSTERN Company: CLARKE CORPORATION Phone: (316) 264-9632

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/19/2016 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4032' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED FROM 2490' & PULLED FROM WELL BORE. RAN 2" TUBING TO 1056' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 640' & SPOTTED 35 SX CEMENT. PULLED TUBING TO 320' & CIRCUALTED TO SURFACE WITH 105 SKS CEMENT. PULLED TUBING & TOPPED OFF CEMENT WITH 10 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4098	4112		

Remarks: COPELAND CEMENT. COMMON CEMENT.

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

MAR - 3 2017