

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-10038-00-01
Spot: NESENE Sec/Twnshp/Rge: 12-24S-16W
3662 feet from S Section Line, 275 feet from E Section Line
Lease Name: HOWELL OWWO Well #: 1
County: EDWARDS Total Vertical Depth: 4065 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N, BLDG 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	4065	375	WITH 130 SX CMT
SURF	10.75	240		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/21/2017 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PUMP BOTTOM WITH 20 SX CMT WITH 100# HULLS. PLUG AT 1050' WITH 10 SX GEL & 50 SX CMT. PLUG AT 270' WITH 60 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2017 5:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

ATTEMPT TO PUMP CMT DOWN 2 7/8", HOLE IN TBG, WASH OUT CMT. TRY TO SET CIBP. COULD NOT GET BY 610'. CMT PLUG. RAN 2 3/8" TBG BESIDE 2 7/8" DOWN TO 1058'. AT 1058' PUMP 50 SX CMT. GOOD CIRCULATION. AT 405' PUMP 275 SX CMT. CMT CIRCULATED. PULL TBG & TOP OFF WITH 15 SX CMT. HOLE STAYING FULL. 2/22/17: CHECK CMT TOP & HOLE FULL.

Perfs:

Top	Bot	Thru	Comments
4050	4060		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
FEB 24 2017
KCC DODGE CITY *MD*

Form CP-2/3

INVOICED

MAR - 3 2017