

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-20869-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 6-24S-15W
209 feet from S Section Line, 4767 feet from E Section Line
Lease Name: RUDD Well #: 1-6
County: STAFFORD Total Vertical Depth: 4036 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N, BLDG 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3980		WITH 2 SX CMT
PROD	4.5	4036	2020	WITH 220 SX CMT
SURF	8.625	327		WITH 215 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/23/2017 1:00 PM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: KENT DEUTSCH Company: DEUTSCH OIL Phone: (316) 681-3567

Proposed Plugging Method: CIBP @ 3980' WITH 2 SX CMT. PLUG AT 1030' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2017 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3980' WITH 2 SX CMT PLACED ON TOP. 1ST PLUG AT 1030' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 50 SX CMT. FILL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4036	4042	OH	

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed

Ken Scofield

(TECHNICIAN)

RECEIVED
FEB 24 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
MAR - 3 2017