

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21674-00-00
Spot: SWNE Sec/Twnshp/Rge: 36-10S-17W
4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: WHISMAN Well #: 7
County: ROOKS Total Vertical Depth: 3556 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3498		0 SX
SURF	8.625	221		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2017 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL COMPANY, INC. D Phone: (620) 793-2672

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Knock out bridge plug at 3200'.
Production perforations: 3240' - 3407'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2017 7:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1840', 1140', 650' and 250'. Ran tubing to 3180' and pumped 110 sx cement w/200 # hulls. Pulled tubing to 1840' and pumped 80 sx cement w/100 # hulls. Pulled tubing to 650' and pumped 40 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/20 sx cement. Visually checked 8 5/8" x 4 1/2' annulus and cement was to surface.

GPS: 39.14459N -099.16326W

Perfs:

Top	Bot	Thru	Comments
3380	3407		
3312	3316		
3306	3310		
3282	3288		
3257	3262		
3240	3246		

KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENTING TICKET # 44567

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

FEB 13 2017

INVOICED

Form CP-2/3

MAR - 2 2017