

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-20355-00-00  
Spot: NENENE Sec/Twnshp/Rge: 25-34S-33W  
380 feet from N Section Line, 380 feet from E Section Line  
Lease Name: INGLAND TWIN Well #: 1  
County: SEWARD Total Vertical Depth: 6075 feet

Operator License No.: 34434  
Op Name: EDISON OPERATING COMPANY LLC  
Address: 8100 E. 22ND ST. N., BLDG 1900  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6075	1816	WITH 100 SX CMT
SURF	8.625	1519		WITH 600 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2017 4:30 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5950' WITH 2 SX CMT. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 02/08/2017 6:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

TOF AT 4680'. PUMPED 50 SX CMT WITH 200# HULLS. TAGGED TOC @ 3850'. 1ST PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 592' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 35 SX CMT. 2/10/17: CMT FELL BACK TO 235'. TOPPED OFF WITH 2 YDS CMT.

Top	Bot	Thru	Comments
6000	6022		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY BASIC.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
FEB 20 2017  
KCC DODGE CITY

INVOICED  
MAR - 3 2017

Form CP-2/3