

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23651-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 30-7S-21W
2015 feet from N Section Line, 520 feet from E Section Line
Lease Name: BELLEAU Well #: 1
County: GRAHAM Total Vertical Depth: 3750 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3745		170 SX
SURF	8.625	218		170 SX
T1	2.375	3696		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2017 8:30 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. DBA Phone: (785) 483-8355

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 11 sx gel and 600 # hulls.
Port Collar at 1730' w/210 sx cement.
Perforations: 3354' - 3356', 3435' - 3438' and 3444' - 3447'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3556' and pumped 11 sx gel followed by 50 sx cement w/250 # hulls. Pulled tubing to 1895' and pumped 180 sx cement w/100 # hulls. Pulled tubing. Topped off casing with 30 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 200 psi.

GPS: 39.41745 -099.69743

Perfs:

Top	Bot	Thru	Comments
3444	3447		
3435	3438		
3354	3356		


KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: QUALITY OILWELL TICKET # 7335

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

INVOICED

Form CP-2/3

FEB 16 2017

MAR - 3 2017