

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-30224-00-00
Spot: SENWNW Sec/Twnshp/Rge: 8-10S-17W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: WINTERS C Well #: 2
County: ROOKS Total Vertical Depth: 3560 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
LI	2.375	3556		
PROD	4.5	3558		275 SX
SURF	8.625	150		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2017 8:30 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Revd. from: LENNY DINKEL Company: GORE OIL COMPANY DBA Phone: (785) 259-1928

Proposed Plugging Method: Ordered 180 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Lans - 3415' - 3509'
1910' TOF rods and pump.
2 3/8" tubing cemented in hole. Gore has no record.
110 joints tubing. Packer and tail pipe to 3500'. Old Squeezed jobs 998' - 1029' to surface.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2017 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated a 6 shot perf at 1900'. Global rigged to 2 3/8" tubing and pumped 120 sx cement w/250 # hulls mixed to pump 2 3/8" tubing to pressure with 500 psi. Shut in pressure 100 psi. Rigged to 8 5/8" surface casing and pumped 35 sx cement with 300 psi. Shut in pressure 300 psi.

GPS: 39.20246 -099.24814

Perfs:

Top	Bot	Thru	Comments
3415	3509		

KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: GLOBAL CEMENTING CO TICKET # 2732

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

FEB 09 2017

INVOICED

MAR - 3 2017