

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-20391-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 8-10S-17W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: WHITE A Well #: 2  
County: ROOKS Total Vertical Depth: 3550 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	3.5	3462		125 sx
PROD	4.5	3546		525 SX
SURF	8.625	157		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/07/2017 12:45 PM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY DBA Phone: (785) 259-1928

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perf Lans: 3276' - 3468', 3378' - 3445'.  
DV Tool at 1320' w/350 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/07/2017 1:45 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Global rigged to 3 1/2" liner and pumped 125 sx cement w/500 # hulls mixed in to pressure with 800 psi. Shut in pressure 500 psi. Rigged to 8 5/8" surface casing and pumped 5 sx cement pressured to 500 psi. Shut in pressure 500 psi.

GPS: 39.20245 -099.23880

**Perfs:**

Top	Bot	Thru	Comments
3378	3449		

**KCC WICHITA**  
**FEB 24 2017**  
**RECEIVED**

Remarks: GLOBAL CEMENTING CO. TICKET # 2733

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

CM

FEB 03 2017

INVOICED Form CP-2/3

MAR - 8 2017