

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-071-20035-00-00  
Spot: NE Sec/Twnshp/Rge: 27-20S-40W  
4117 feet from S Section Line, 1288 feet from E Section Line  
Lease Name: DRAKE Well #: 1  
County: GREELEY Total Vertical Depth: 2955 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 110 W LOUISIANA STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2954	0	WITH 450 SX CMT
SURF	8.625	286		WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/07/2017 8:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: RUN TBG TO 2800' & SPOT 60 SX CMT WITH 200# HULLS. PULL TBG TO 1500' & SPOT 80 SX CMT WITH 250# HULLS. WAIT 2 HOURS & TAG TOC. IF ABOVE 1000' RUN TBG TO 500' & CIRCULATE CMT TO SURFACE. FILL THE ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/07/2017 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 60 SX CMT WITH 200# HULLS AT 2808'. FULL CIRCULATION. PUMP 80 SX CMT WITH 250# HULLS AT 1510' TO SHUT OFF CASING LEAK, FULL CIRCULATION. CIRCULATE CMT FROM 500' TO 0' WITH 60 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:


Top	Bot	Thru	Comments
2810	2820		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
FEB 22 2017  
KCC DODGE CITY



5A

INVOICED Form CP-2/3

MAR - 8 2017