

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20670-00-00
Spot: NWSW Sec/Twnshp/Rge: 20-20S-39W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: MARVEL Well #: 1A
County: GREELEY Total Vertical Depth: 2840 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2839	0	WITH 525 SX CMT
SURF	8.625	271		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/10/2017 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: RUN TBG TO 2800' & SPOT 60 SX CMT WITH 200# HULLS. PULL TBG TO 1500' & SPOT 80 SX CMT WITH 250# HULLS. WAIT 2 HOURS & TAG TOC. IF ABOVE 1000' RUN TBG TO 500' & CIRCULATE CMT TO SURFACE. FILL THE ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2017 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG & RODS STUCK IN HOLE. CANNOT FISH RODS. RAN STRING SHOT DOWN 2 3/8" X 4 1/2" ANNULUS. TAGGED AT 1520'. SHOT STRING SHOT AT 1460'-1495'. TBG BACKED OFF AT 1496'. PULL TBG WITH RODS STUCK INSIDE. LEFT APPROXIMATELY 1300' OF 2 3/8" TBG & RODS IN WELL. RAN GOOD TBG BACK TO 1492'. LOAD HOLE WITH 9 BBLs WATER. SPOT 70 SX CMT WITH 200# HULLS AT 1492' TO 400'. FULL RETURNS. PULL TBG TO 375' & CIRCULATE CMT TO SURFACE WITH 25 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 5 SX CMT DOWN THE 4 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2807	2816		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN) INVOICED

RECEIVED
FEB 22 2017
KCC DODGE CITY

Form CP-2/3