

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20073-00-00
Spot: NE Sec/Twnshp/Rge: 28-20S-40W
3968 feet from S Section Line, 1343 feet from E Section Line
Lease Name: HOUSEHOLDER Well #: 1
County: GREELEY Total Vertical Depth: 2835 feet

Operator License No.: 4894
Op Name: HORSESHOE OPERATING, INC.
Address: 110 W LOUISIANA STE 200
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1335		
PROD	4.5	2839	0	WITH 100 SX CMT
SURF	8.625	243		WITH 160 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/06/2017 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd, from: PHELPS WHITE Company: HORSESHOE OPERATING Phone: (620) 847-8267

Proposed Plugging Method: Procedure(from KCC)1. Attempt to release pkr & TOOH. If unsuccessful, cut or back off below 2400'2. CIBP w/ 2 sx @ 2400'3. CIBP @ 1325'4. Test csg to 700 #(if no test will use pkr to cmt)5. Perf 4 holes @ 1300'6. Spot 80 sx cmt (approx. 25 sx inside csg & 55 sx outside csg w/ 50# hulls in last 25 swx)7. Perf @ 275' & circ cmt to surface.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/06/2017 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT WITH 200# HULLS AT 2407'. TAG TOC WITH ELECTRIC LINE AT 1340'. CIBP @ 1335' TO SHUT OFF CASING LEAK. TEST CASING TO 750#. HOLDING. PERFORATE 4 HOLES AT 1325'. INJECTION RATE WITH WATER 2 BPM AT 1100 PSI. PUMP 80 SX CMT AT 1100 TO 800 PSI. DISPLACE WITH 11 BBLs WATER LEAVING 40 SX CMT INSIDE THE CASING & 40 SX CMT OUTSIDE THE CASING. NO BLOW OR CIRCULATION UP ANNULUS. PERFORATE 4 HOLES AT 275' & CIRCULATE CMT TO SURFACE WITH 85 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2806	2813		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed *[Signature]*
SA (TECHNICIAN) VOICED

RECEIVED
FEB 22 2017
KCC DODGE CITY *[Signature]*

MAR - 3 2017 Form CP-2/3