

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21961-00-00
Spot: NWNESE Sec/Twnshp/Rge: 1-28S-6W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: HIRT Well #: 1-1
County: KINGMAN Total Vertical Depth: 3968 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3968 | 2760 | 185 SX |
| SURF | 8.625 | 289 | | 190 SX |
| T1 | 2.875 | 3779 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2016 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: DARIN DRESSEL, JAY SCH Company: LARIO OIL & GAS COMPANY Phone: (620) 297-3222

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/02/2016 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3750' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED FROM 2760' & PULLED TO 850' WHERE 50 SKS CEMENT WAS SPOTTED. TAGGED CEMENT AT 740'. PULLED CASING TO 350' & CIRCUALTED CEMENT TO SURFACE WITH 145 SX CEMENT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3800 | 3810 | | |

Remarks: QUALITY WELL SERVICE. COMMON CEMENT. DENIED TA

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

JK