

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-01136-00-00
Spot: N2NENE **Sec/Twnshp/Rge:** 4-19S-2W
4950 feet from S Section Line, 660 feet from E Section Line
Lease Name: LARSON B **Well #:** 1
County: MCPHERSON **Total Vertical Depth:** 2979 feet

Operator License No.: 32731
Op Name: LEWIS OIL & GAS OF GALVA, INC.
Address: PO BOX 195
GALVA, KS 67443

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| PROD | 5 | 2963 | | 0 SX |
| SURF | 8 | 215 | | 0 SX |

Well Type: OIL **UIC Docket No:** _____ **Date/Time to Plug:** 01/10/2017 12:00 AM
Plug Co. License No.: 30280 **Plug Co. Name:** SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: GREGORY LEWIS **Company:** LEWIS OIL & GAS OF GALVA **Phone:** (620) 654-8414

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ **WitnessType:** COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2017 11:45 AM **KCC Agent:** JERRY SPARLING

Actual Plugging Report:

TAGGED BOTTOM @ 2979 FT. SANDED BACK WITH WATER TO 2912 FT. RAN BAILER AND TAGGED @ 2900'. PUT 5 SX CEMENT ON TOP WITH DRUM BAILER. TRIED TO PULL 5.5" NO MOVEMENT. PERFORATED 5.5" @ 450 FT. RAN 2.375 DOWN CASING, RAN 125 FT OF 1" DOWN BACKSIDE, RAN CEMENTED TO SURFACE 25 SX AND TIED ON TO 2 3/8" PUMPED 70 SX TO SURFACE. RAN BAILER, TAGGED AT 250 FT. MIXED UP 10 SX AND FILLED CASING.

Perfs:

| Top | Bot | Thru | Comments |
|-----|------|------|----------|
| 215 | 2979 | | |

Remarks: TA NOV, SUBMITTED TO LEGAL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

Form CP-2/3

1/17

✓