

1-19

040219

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,064-0000

NE SW NW, SEC. 27, T 22 S, R 13 W/E

3630 feet from S section line

4290 feet from E section line

Lease Name McMillan Well # 2

County Stafford 12/6.98

Well Total Depth 3907 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 345

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Operator: Grady Bolding Corporation

Name & Address Box 244

Great Bend, KS 67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:15 p.m. Day: 19 Month: 1 Year: 19 89

Plugging proposal received from Jerry Allen

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3899' PBDT 3870' Perfs at 3847-48' Top Elevation 1904' KB

1st plug sand back to 3800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

RECEIVED STATE CORPORATION COMMISSION

1-24-89

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations Observed by Agent?: All Part _____ None _____

Operations Completed at _____ Hour: 1 p.m. Day: 19 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sand back to 3800' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2136.55' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-25-89

INV. NO. 23779

Signed Stephen J. Pfeifer (TECHNICIAN)