

8-16

To: 1120287
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,298-0000
100' SW
SW SW NW, SEC. 27, T 22 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Operator: Grady Bolding Corporation
Name &
Address Box 244
Great Bend, KS 67530

2920 feet from S section line

5000 feet from E section line

Lease Name McMillan Well # 5

County Stafford 123.50

Well Total Depth 3800 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 16 Month: 8 Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 3689' Perfs at 3461-63'

1st plug sand back to 3410' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 16 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3410' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2186' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 8-24-89

AUG 23 1989

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 25731