

8-16

To: 120288
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,294-0000
200' SW NW
SW NW, SEC. 27, T 22 S, R 13 W/E
3530 feet from S section line
5050 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383
Operator: Grady Bolding Corporation
Name &
Address Box 244
Great Bend, KS 67530

Lease Name McMillan Well # 4
County Stafford 120.25
Well Total Depth 3700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 16 Month: 8 Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 3699' PBD 3692' Perfs at 3458'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 16 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sand back 4 1/2" casing to 3400' and dumped 4 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-450 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2218' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-24-89
INV. NO. 25730

observe this plugging.
STATE CORPORATION COMMISSION

AUG 23 1989

Signed Duane Rankin
(TECHNICIAN)