

1 050478

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

SW NE SW, SEC. 27, T 22 S, R 13 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Brodie Well # 1

Operator: Rains & Williamson Oil Co., Inc. County Stafford
Name & Address 435 Page Court
220 W. Douglas
Wichita, KS 67202

Well Total Depth 3849 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 368 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 11 Month: March Year: 19 85

Plugging proposal received from Clay Duntz
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 3847' Open Hole

1st plug sand back to 3800' and dump 5 sx cement on top of sand
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
and 100 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 11 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3800' and dumped 5 sx cement on top
of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1985 3-15-85

Maximum pressure 500 psi and shut in 200 psi CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. Recovered 2785' 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / ~~not~~) observe this plugging.

DATE 3-18-85

Signed Richard W. Gacy (TECHNICIAN) 50

INV. NO. 7371