

To: 1 040551
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-15
API NUMBER 13-185-21,278-0000

204
SE, SE, NE, SEC. 28, T. 22 S, R. 13 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Ruth Walls A Well # 1

Operator: L.D. Drilling, Inc.

County Stafford 125.38

Name & Address RR 1, Box 183B

Well Total Depth 3858 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Saturn Well Service Corp. License Number 3641

Address RR 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: 7 Year: 19 91

Plugging proposal received from Mike Kasselmann

(company name) Saturn Well Service Corp. (phone) 316-793-3051

were: 4 1/2" at 3857' w/175 sx cement, Perfs at 3464-68, 3586-92'

1st plug sand back to 3400' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 15 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3400' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 210 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-8-91

INV. NO. 32601

STATE CORPORATION COMMISSION
observe this plugging

JUL 24 1991

Signed Stephen J. Pfeiffer
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84