

To: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

API NUMBER 15-053 20-118.00.00

NW, Sec. 29, T 14S, R 10 WE  
330 feet from N section line  
2310 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5462

Lease Name E. Soukup Well # 1

Operator: L.G. Stephenson & Co. Inc.  
 Name & Address 670 E. Side Financial Center  
7701 E. Kellogg  
Wichita, Kansas 67207

County Ellsworth  
 Well Total Depth 2915 feet 94.74  
 Conductor Pipe: Size        feet  
 Surface Casing: Size 8 7/8 feet 196

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D&A       

Other well as hereinafter indicated       

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:30 A Day: 5 Month: 6 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Neal Peddicord

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Sand hole to 2750' and cement with 4 sacks.

Squeeze hole with 4 sacks hulls, 25 sacks 50/50 Pozmix w/4% gel,  
12 sacks Bentonite, 40 sacks 50/50 Pozmix w/4% gel, 3 sacks Bentonite,  
1 sack hulls, 8 7/8" Plug, and 100 sacks 50/50 Pozmix w/4% gel.

Signed [Signature]  
 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part        None       

Operations Completed: Hour: 1:30 PM Day: 5 Month: 6 Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with sand to 2750' and cemented  
with 4 sacks cement w/ dump bailer.

Hole squeezed with 4 sacks hulls, 25 sacks 50/50 Pozmix w/4% gel,  
12 sacks Bentonite, 40 sacks 50/50 Pozmix w/4% gel, 3 sacks  
Bentonite, 1 sack hulls, 8 7/8" plug and 100 sacks 50/50 Pozmix  
w/4% gel pumped into 8 7/8" surface casing.

Remarks: 4 1/2" - 2914 Perfs 2868-72 2802-08

1988' of 4 1/2" casing recovered

Allied Cementing Co., Inc. Ticket # 37637

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 13 1984

CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
 and that I (did / ~~did not~~) observe this plugging.

INVOICED

DATE 6-13-84  
 INV. NO. 1992  
6-5

Signed [Signature]  
 (TECHNICIAN)