

1 060504

1189.00.00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,156
C NE SE, SEC. 16, T 23 S, R 23 W/E

1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Oliphant Well # 1

Operator: Berexco, Inc.

County Hodgeman 156,49

Name & Address 970 Fourth Financial Center

Well Total Depth 4815 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 517

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 11 Month: March Year: 19 85

Plugging proposal received from Gary Marshall

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1540' with 50 sx cement

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 700' with 70 sx cement
solid bridge

MAR 15 1985

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

CONSERVATION DIVISION
Wichita, Kansas

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:15 pm Day: 11 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement, 2nd plug at 700' with 70
sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to
circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun # 264013
additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-4-85

INV. NO. 75260

3-11

Signed Paul A. Luthi
(TECHNICIAN)