

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22328-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 22-15S-21W
4500 feet from S Section Line, 2270 feet from E Section Line
Lease Name: HIGH PLAINS DRIFTER Well #: 1
County: TREGO Total Vertical Depth: 4300 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4285		150 SX
SURF	8.625	269		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/30/2015 9:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: KEITH BRIGHT Company: CMX, INC. DBA Phone: (316) 239-8593

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 400 # hulls and 19 sx gel.
Perforations: 4038' - 4041'.
DV Tool at 1551' w/375 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2015 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3979' and pumped 19 sx gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 1714' and pumped 200 sx cement. Good circulation of cement. Pulled tubing out. Topped off with 35 sx cement. Tied on to backside and squeezed with 40 sx cement. Shut in pressure 200 psi.

GPS: 38.73782 -099.64257

Perfs:

Top	Bot	Thru	Comments
4038	4041		


KCC WICHITA
FEB 24 2017
RECEIVED

Remarks: ALLIED CEMENT TICKET # 65586

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM