

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20560-00-01
Spot: NENWSWSW Sec/Twnshp/Rge: 34-18S-29W
1011 feet from S Section Line, 4917 feet from E Section Line
Lease Name: MCWHIRTER Well #: 1-SWD
County: LANE Total Vertical Depth: 2185 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2179	0	WITH 375 SX CMT
SURF	8.625	371		WITH 250 SX CMT

Well Type: SWD UIC Docket No: D27309.0 Date/Time to Plug: 02/13/2017 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Revd. from: TOM LARSON Company: LARSON OPERATING Phone: (620) 653-7368

Proposed Plugging Method: SQUEEZE PERFS WITH 30 SX CMT & 200# HULLS. RTIH TO 1300' & CIRCULATE CMT TO 0'. CHECK BACKSIDE TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2017 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

RAN TBG TO 1728' & PUMPED 30 SX CMT WITH 100# HULLS. PULLED TBG TO 1320' & CIRCULATED CMT TO SURFACE WITH 85 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. PRESSURED BACKSIDE TO 500# WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1735	1885		

INVOICED
FEB 23 2017

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
FEB 15 2017
KCC DODGE CITY 