

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-20182-00-00  
Spot: NENENE Sec/Twnshp/Rge: 13-27S-15W  
5056 feet from S Section Line, 426 feet from E Section Line  
Lease Name: JONES DEVELOPMENT Well #: C3  
County: PRATT Total Vertical Depth: 4310 feet

Operator License No.: 3180  
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI  
Address: 8100 E 22ND ST N, BLDG 600  
WICHITA, KS 67226

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| PROD   | 4.5   | 4310       | 0           | WITH 200 SX CMT |
| SURF   | 8.625 | 300        |             | WITH 250 SX CMT |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/10/2017 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2017 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

2/9/17: WHILE ATTEMPTING TO PUSH DEAD ANIMAL THAT HAD FELL INTO WELL DUE TO NO SURFACE CONTROL DOWN HOLE RAN 2 JOINTS OF TBG & SAND LINE OUT SIDE OF CASING AT 980'. PARTED SAND LINE WHILE ATTEMPTING TO GET BACK INSIDE OF CASING LEAVING 2 JOINTS OF 2 3/8" TBG & 100' OF 5/8" SAND LINE IN HOLE. WERE UNABLE TO STAY INSIDE OF CASING TO PUT IN BOTTOM PLUG. FLUID LEVEL AT 200' FROM SURFACE. SHUT DOWN.  
2/10/17: RUN TBG INTO 920' & SPOTTED 35 SX COMMON CEMENT WITH 3% CC. LAID TBG DOWN. LET CMT SET. TAGGED TOC @ 800', PERFORATE 4 1/2" CASING AT 330'. RUN TBG INTO 320'. PUMPED DOWN TBG WITH 265 SX CMT CIRCULATING 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS TO SURFACE WITH CMT. LAID DOWN TBG. TOPPED WELL OFF WITH 20 SX CMT. 2/14/17: TOPPED OFF 4 1/2" CASING WITH 35 SX CMT. TOPEED OFF 4 1/2" X 8 5/8" ANNULUS WITH 10 SX CMT. PRESSURED TO 200#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4102 | 4104 |      |          |

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED COMMON CEMENT WITH 3% CC & 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
FEB 15 2017  
KCC DODGE CITY

INVOICED  
FEB 23 2017  
Form CP-2/3