

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20044-00-00
Spot: SESE Sec/Twnshp/Rge: 12-27S-15W
474 feet from S Section Line, 440 feet from E Section Line
Lease Name: HALPER Well #: 1
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 3180
Op Name: DEUTSCH, KENT A. DBA DEUTSCH OI
Address: 8100 E 22ND ST N, BLDG 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4500	0	WITH 200 SX CMT
SURF	8.625	331		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/09/2017 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3890' WITH 4 SX CMT. PERFORATE AT 1020' WITH 50 SX CMT 100# HULLS IN LAST 25 SX CMT. PERFORATE AT 360' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2017 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3871' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PERFORATE 4 1/2" CASING AT 1020' & 360'. RUN TBG TO 1020'. PUMPED DOWN TBG WITH 25 SX CMT 100# HULLS & 25 SX CMT. PULLED TBG TO 360'. PUMPED 140 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE INSIDE THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS. LAID DOWN TBG. TOPPED OFF WITH 10 SX CMT. 2/14/17: TOPPED OFF 4 1/2" CASING WITH 15 SX CMT. TOPPED OFF 4 1/2" X 8 5/8" ANNULUS WITH 10 SX CMT. PRESSURED TO 200#.

Perfs:

Top	Bot	Thru	Comments
4448	4486		
3942	4172		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)
SA

RECEIVED
FEB 15 2017
KCC DODGE CITY

INVOICED
FEB 23 2017

Form CP-2/3