

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-20968-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 34-23S-4W  
2330 feet from S Section Line, 440 feet from E Section Line  
Lease Name: MCELWAIN Well #: 4  
County: RENO Total Vertical Depth: 3590 feet

Operator License No.: 5330  
Op Name: EXCALIBUR PRODUCTION COMPANY,  
Address: 1016 N MAIN PO BOX 278  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3425		
11	8.625	566		
PROD	5.5	3589	626	135 SX
SURF	12.75	260		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/22/2016 12:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: MARK DANNER Company: EXCALIBUR PRODUCTION Phone: (620) 242-7918

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/23/2016 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP AT 3345' / SPOTTED 2 SX CEMENT ON PLUG. SHOT 5 1/2" CASING OFF AT 626', PULLED CASING. TRIPPED IN WITH 2 7/8" TUBING - 650'. MIXED 50 SX CEMENT, 200 LBS. COTTONSEED HULLS. PULLED TUBING UP TO 350', WAITED 2 HOURS, TAGGED CEMENT AT 400', CIRCULATED CEMENT TO SURFACE WITH 155 SX CEMENT, 50 LBS. HULLS.

Perfs:

Top	Bot	Thru	Comments
3385	3387		

Remarks: COPELAND OUT OF BURRTON, PROVIDED CEMENT, TICKET #44829

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)

INVOICED Form CP-2/3  
FEB 23 2017 12/7