

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-057-20867-01-00
Spot: NENWNWNW Sec/Twnshp/Rge: 24-29S-22W
5231 feet from S Section Line, 4897 feet from E Section Line
Lease Name: JAMES 2922 Well #: 1-13H
County: FORD Total Vertical Depth: 5293 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5250		WITH 100 SX CMT
COND	20	90		WITH 10 SX CMT
	11 7	9999	0	
PROD	7	5681	1674	WITH 300 SX CMT
SURF	9.625	918		WITH 355 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/16/2017 2:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5250' WITH 100 SX CMT. PLUG AT 1600' WITH 75 SX CMT. PLUG AT 950' WITH 100 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 02/16/2017 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5250'. CIRCULATED HOLE WITH 190 BBL MUD THEN SPOTTED 100 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1600' WITH 75 SX CMT. 2ND PLUG AT 950' WITH 100 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8473	8798		
7997	8348		
7552	7886		
7132	7454		
6672	6976		
6282	6564		
5880	6206		
5460	5800		
536	9430		

INVOICED
FEB 23 2017

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ORR ENTERPRISES. TMD= 10,120'

Plugged through: TBG

District: 01

RECEIVED
FEB 17 2017
KCC DODGE CITY

Signed [Signature]
SA (TECHNICIAN)