

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21524-00-00
Spot: SWSWSWSE Sec/Twnshp/Rge: 10-35S-21W
183 feet from S Section Line, 2575 feet from E Section Line
Lease Name: SNAKE CREEK RANCH Well #: 1-10
County: CLARK Total Vertical Depth: 5997 feet

Operator License No.: 34322
Op Name: STRAT LAND EXPLORATION CO
Address: 15 E. 5TH ST., STE 2020
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 10 SX CMT
CIBP		5750		WITH 10 SX CMT
COND	20	60		WITH 57 SX CMT
PROD	4.5	5996	2508	WITH 350 SX CMT
SURF	8.625	1516		WITH 705 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/06/2017 11:00 AM
Plug Co. License No.: 35195 Plug Co. Name: SURE ENERGY SERVICE, LLC
Proposal Revd. from: GRANT YATEMAN Company: STRAT LAND EXPLORATION Phone: (806) 435-0411

Proposed Plugging Method: CIBP @ 5750' WITH 2 SX CMT. CIBP @ 5600' WITH 2 SX CMT. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 02/08/2017 4:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

2/6/17: SET CIBP @ 5750' WITH 10 SX CMT. SET CIBP @ 2600' WITH 10 SX CMT.
2/8/17: 1ST PLUG RAN TBG TO 1560' & PUMPED 15 SX GEL & 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5808	5816		

INVOICED

FEB 23 2017

Remarks: USED 60/40 POZMIX 4% GEL BY SURE ENERGY.

Plugged through: TBG

District: 01

RECEIVED
FEB 13 2017
KCC DODGE CITY

Signed

[Signature]
(TECHNICIAN)