

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21852-00-00
Spot: SESESENW Sec/Twashp/Rge: 25-16S-27W
2661 feet from S Section Line, 2940 feet from E Section Line
Lease Name: MCBEE B Well #: 1-25
County: LANE Total Vertical Depth: 4660 feet

Operator License No.: <u>9408</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>TRANS PACIFIC OIL CORPORATION</u>	DVT		2132		WITH 350 SX CMT
Address: <u>100 S MAIN STE 200</u>	PROD	4.5	4640	0	WITH 225 SX CMT
<u>WICHITA, KS 67202</u>	SURF	8.625	309		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/13/2017 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: MONTE Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: TUN TBG TO BOTTOM & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 50' BELOW DV TOOL & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2017 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3995' & PUMPED 35 SX CMT & 100# HULLS. PULLED TBG TO 2190' & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4066	4071		

Remarks: USED 60/40 POZMIX 4% GEL BY SWFIT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

SA

RECEIVED
FEB 14 2017
KCC DODGE CITY

Form CP-2/3

INVOICED
FEB 23 2017