

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21133-00-00
Spot: SWNENW Sec/Twnshp/Rge: 34-16S-7W
4180 feet from S Section Line, 3580 feet from E Section Line
Lease Name: JANSSEN FARMS Well #: 1-34
County: ELLSWORTH Total Vertical Depth: 2545 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2306	1040	150 SX
SURF	8.625	266		175 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/30/2016 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 727-6964

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 11/30/2016 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PUMPED 30 SX'S WITH 3% CC AND 100#S COTTON HULLS AT 2100'. PULLED TUBING ON OUT. LET SET AWHILE AND TAGGED AT 1750'. CUT CASING LOOSE AT 1040' AND PULLED TO 850' AND PUMPED 35 SX'S WITH 3% CC AND 100#S COTTON HULLS. PULLED CASING UP TO 550' AND LET SET AWHILE. TAGGED CEMENT AT 710'. PUMPED 35 SX'S AT 550', PULLED CASING TO 315' AND CIRCULATED CEMENT TO SURFACE. PULLED CASING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
2148	2186	CSG	

Remarks: QUALITY OILWELL CEMENT TICKET #6585.

Plugged through: CSG

INVOICED
FEB 23 2017

District: 02

Signed Virgil Clothier
(TECHNICIAN)

JK