

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-031-22103-00-00
Spot: NENWSE Sec/Twnshp/Rge: 29-22S-14E
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: OCHS Well #: 1
County: COFFEY Total Vertical Depth: 1850 feet

Operator License No.: 33453
Op Name: JONES, STEPHEN C.
Address: 2332 W NEW ORLEANS
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1722		
PROD	4.5	1804		250 SX
SURF	8.625	40		30 SX
T1	2.375	1820		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2017 1:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STEVE JONES Company: _____ Phone: (918) 286-1499

Proposed Plugging Method: Fill with cement according to Kansas Corporation Commission instructions.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE
Date/Time Plugging Completed: 02/15/2017 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1688', pumped 20 sxs cement, pull tubing to 600', pumped 10 sxs cement, pulled tubing to 260', pumped 32 sxs cement to surface, gel spacers between cement plugs, topped off well w/19 sxs cement.

Perfs:

Top	Bot	Thru	Comments
1795	1802		
1724	1730		

RECEIVED
KCC DIST # 3
FEB 27 2017
CHANUTE, KS

INVOICED
MAR - 3 2017

MH
KCC WICHITA
MAR 02 2017
RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

