



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 12 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wynn of Thunderbird has this

date requested permission to plug the following described well:

Mr. Wynn guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drlg. Co.

Complete Address: Box 18407, Wichita, Kansas

Lease Name: MacNair "C" Well No. 1

Location: C NW NE Sec. 10 Twp. 22 Rge. 24 XX (E) (W)

County: Hodgeman Total Depth 4745' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Wynn was instructed to plug the well as follows:

8 5/8" to 563' circulated w/ cement. Mud 4745' to 600'

Spot 70 sacks cement 600' to 400' Mud 400' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edgar J. Eves  
Conservation Division Agent